

**Kerala Paper Products Limited**  
(Government of Kerala Undertaking)

NEWSPRINT NAGAR P.O.,  
KOTTAYAM (DIST.)  
KERALA - 686616. INDIA.  
Web :www.keralapaper.in  
CIN: U21013KL1983GOI003735

INVITATION TO TENDER

14.11.2023

To,  
M/s.....  
.....

Inquiry No. : KPPL/CP/FE/ELE/1646  
Tender Due Date: 16.11.2023  
Email ID: [tenders@kpplonline.in](mailto:tenders@kpplonline.in)

Dear

We invite you to submit your quotation for the following goods by e-mail in PDF format indicating our Inquiry No. and due date to [tenders@kpplonline.in](mailto:tenders@kpplonline.in), before due date, ie on 16.11.2023 and bids shall be opened on the same day.

Sl No	Item Name/ Description	Unit	Qty
1	STARTER PANEL 75 KW (AS PER ANNEXURE)	NOS	1
2	STARTER PANEL 110 KW (AS PER ANNEXURE)	NOS	1

Terms of Delivery: Free Delivery at our KPPL Store.

Terms of Payment: Within 30 days after receipt subject to acceptance.

Delivery required in case of placement of an Order based on this enquiry: **1 day**


Your offer should be specific with following break-up:-

- |                   |   |                   |
|-------------------|---|-------------------|
| 1. Basis of price | 4. GST  | 7. Delivery Time: |
| 2. Basic Price    | 5. Discount offered %                         |                   |
| 3. Excise Duty %  | 6. Other charges%(Like<br>P & F, Freight etc) |                   |

You may please indicate the tender number as the subject of the mail.

Yours faithfully  
For Kerala Paper Products Ltd.

AUTHORISED SIGNATORY



**DIRECT ONLINE STARTER PANELS**

**1. 110 KW Rating with the following switch gears**

MCCB/SFU	: 400 A	Make: Siemens , L&T or any reputed make.
Contractor	: 300 A	Make: Siemens , L&T or any reputed make.
OL Relay (CT Operated)	: 135-225A	Make: Siemens , L&T or any reputed make.

CT for metering

- ON, OFF and Emergency stop Push buttons (Reputed make) on panel.
- ON&OFF LED Indications to be provided on the panel.
- 6A MCB for control supply isolation to be provided.
- Adequately rated link to be provided for neutral supply.
- 2.5 sq mm elemex connectors to be provided for control connections.
- All panel interconnections to done with copper bus bars/cables of adequate size.
- Provision for external interlock to be provided in the control circuit.
- Ammeter and voltmeter on panel with selector switches (Reputed make)
- Incoming & Outgoing supplies shall be terminated on copper bus bars with size 50X6
- Panel: 16 SWG CRCA RAL 7032 (Siemens Gray)
- Necessary holes to be provided in the gland plate (removable)
- Adequate lighting with LED Tube/fixture (To lit up during panel is in open condition) to be provided in the panel.

**2. 75 KW Rating with the following switch gears**

MCCB/SFU	: 315 A	Make: Siemens , L&T or any reputed make.
Contractor	: 225 A	Make: Siemens , L&T or any reputed make.
OL Relay (CT Operated)	: -90-150	Make: Siemens , L&T or any reputed make.

CT for metering

- ON, OFF and Emergency stop Push buttons (Reputed make) on panel.
- ON&OFF LED Indications to be provided on the panel.
- 6A MCB for control supply isolation to be provided.
- Adequately rated link to be provided for neutral supply.
- 2.5 sq mm elemex connectors to be provided for control connections.
- All panel interconnections to done with copper bus bars/cables of adequate size.
- Provision for external interlock to be provided in the control circuit.
- Ammeter and voltmeter on panel with selector switches (Reputed make)
- Incoming & Outgoing supplies shall be terminated on copper bus bars with size 40X6
- Panel: 16 SWG CRCA RAL 7032 (Siemens Gray)
- Necessary holes to be provided in the gland plate (removable)
- Adequate lighting with LED Tube/fixture (To lit up during panel is in open condition) to be provided in the panel.